

# Latest Version: 6.0

## Question: 1

Site selection is one challenge for the traditional data center

- A. TRUE
- B. FALSE

**Answer: A**

## Question: 2

Unpredictable business, expansion and difficult investment is one of the challenges facing the development of traditional data center business.

- A. TRUE
- B. FALSE

**Answer: A**

## Question: 3

Which system affects the PUE most in Data Center.

- A. Power Distribution system
- B. Cooling System
- C. N/A
- D. Lighting system

**Answer: B**

## Question: 4

Which one is the best PUE in the following:

- A. 1.06
- B. 2
- C. 0.3

D. -0.5

**Answer: A**

[https://en.wikipedia.org/wiki/Power\\_usage\\_effectiveness](https://en.wikipedia.org/wiki/Power_usage_effectiveness)

### Question: 5

Cold/Hot aisle containment is used to solve the problem of heat dissipation in Data Center.

- A. TRUE
- B. FALSE

**Answer: A**

### Question: 6

Modular Data Center is on-demand deployment, which avoids over-investment.

- A. TRUE
- B. FALSE

**Answer: A**

### Question: 7

Which Technologies or solutions can reduce PUE?

- A. Increasing the number of access control systems
- B. Efficient modular UPS
- C. Cold/hot aisle containment
- D. In-row cooling

**Answer: BCD**

### Question: 8

FusionModule2000 is an outdoor smart modular data center solution.

- A. TRUE

B. FALSE

**Answer: B**

FusionModule2000 is an indoor model

### Question: 9

FusionModule1000 is an indoor prefabricated all in-one data center solution.

- A. TRUE
- B. FALSE

**Answer: B**

FusionModule1000A All-in-One Prefabricated Data Center is a green and reliable outdoor data center solution.

### Question: 10

FusionModule1000A series solution meets the TIER 4 requirements if it adopts 2N power supply and distribution system.

- A. TRUE
- B. FALSE

**Answer: B**

(FM1000A does not support Tier 4)

### Question: 11

Depending on different layouts, the batteries can be deployed inside or outside FusionModule2000

- A. TRUE
- B. FALSE

**Answer: A**

### Question: 12

When ATS is in automatic mode, the handle for manual operation must be remove.

- A. TRUE
- B. FALSE

**Answer: A**

### Question: 13

Smart Electricity meter of PDU8000 is abnormal, is it possible that:

- A. The transformation ratio of current or voltage is incorrectly set.
- B. Cables to the voltage collector are not properly connected.
- C. The current transformer is faulty.
- D. The smart electricity is faulty.

**Answer: ABCD**

### Question: 14

Which kind of start-up principle does gas fire extinguishing system have?

- A. Automatic startup
- B. Emergency startup
- C. Safe startup
- D. Manual startup

**Answer: ABD**

### Question: 15

If a fire occurs in the FusionModule1000, the smoke detector and heat detector will send a fire alarm to the fire alarm control panel.

- A. TRUE
- B. FALSE

**Answer: A**